GROUT TIGHT TO DECK

HORIZONTAL WALL REINFORCING @ 16" O.C.

ACOUSTICAL BOARD CEILING 1-HOUR FIRE RATED IN PROJECTION ROOMS.

ACOUSTICAL TILE CEILING

VINYL CORK TILE & 4" VINYL BASE

#4 BAR BENT 12" PLACE IN WALL & FLOOR @ 2'-8" O.C.

HORIZONTAL WALL REINF. @ 16" O.C.

4" VINYL BASE (COVELESS & CARPETING)

FILL BLOCK CORES SOLID W/ GROUT

1/2" ISOLATION MATERIAL

2'-6" BARS IN FOOTING @ CORNER THICKENED SLABS

3/4 2/3 THRU PROJECTION ROOM & ADJOINING OFFICE WALLS
SCALE 1/2" = 1'-0"

BUILT UP ROOFING ON 1½" RIGID INSULATION ON 1½" METAL DECK.

STEEL JOIST

2x4 WOOD CONT. - ANCHOR TO JOIST

VAPOR BARRIER

2x4 @ 16" O.C. W/ 3" BATT INSULATION BETWEEN

2x4 WOOD SCALE - BACK UP TO JOIST @ 4'-0" O.C. - ATTACH TO JOIST

ACOUSTICAL TILE CEILING

CAULK JOINT

¾" PLASTER ON BLOCK

GLAZED BRICK LAID-UP IN VERTICAL RUNNING BOND

HORIZONTAL WALL REINF. @ 16" O.C. W/ SLIDING STRIP ANCHORS FOR BRICK @ 16" O.C.

4'-10½"

10'-10½"

QUARRY TILE FLOOR & BASE

CARPET W.W.

VARIES, 4½" TO 1'-4" WIDE PER

2 2/3 THRU FRONT RADIUS WALL
SCALE 1/2" = 1'-0"

PRE-CAST CONCRETE COPING

PLASTIC FLASHING - EXTEND UNDER & SEAL AT BACK EDGE OF COPING.

CONT. CONCRETE BOND BEAM W/ 5-#5 BARS - CONT. EXCEPT AT CONTROL JOINTS.

SURFACE MTD. INDIVIDUAL LETTERS. EACH SEPARATELY LITE FROM BEHIND. SUPPLIED & INSTALLED BY TENANT. NO EXPOSED WIRING OR CONDUIT ALLOWED.

WATER-PROOF COATING ON BLOCK

OUTLINE OF RECESSED LIGHT FIXTURE

STEEL BEAM W 16" x 11½" R. ON BOTT. WELD STRAP ANCHORED EA FACE OF WEB @ 16" O.C.

WOOD BLOCKING ATTACHED TO BACK FACE OF SIGN BOX.

WATER-PROOF COATING ON BOTTOM OF STEEL BM. (APPROX. ½" DEEP)

"REX" E-PLASTER MOULDING - CUT - HOLD DOWN APPROX ½" BELOW STEEL LINTEL BM.

TO LOBBY FLR. ELEV.

LIGHT FIXTURE

2x4 @ 16" O.C.

"REX" ALUM. VENTED SCREED

SEALANT JOINT

¼" CEMENT PLASTER ON METAL LATH

½" PKL. PLATE GLASS

ALUMINUM DOOR W/ INTERMEDIATE MULLION & ½" TEMP. PK. GLASS

ALUMINUM THRESHOLD SET IN MASTIC

4" COVELESS VINYL BASE

6"x6" QUARRY TILE

2'-7"

5 TILES + 4 JOINTS

2" ISOLATION JOINT MATERIAL

#5 BAR @ TOP & BOTTOM OF FOUNDATION WALL

4" CONC. SLAB W/ 6"x6"-6/6 W.W.F.

1 1/2 3 THRU FRONT ENTRANCE & CANOPY
SCALE 1/2" = 1'-0"

GLAZED BRICK LAID IN HORIZONTAL RUNNING BOND ON BACK & SIDES OF 1'-4" x 6'-0" MASONRY PIERS

GLAZED BRICK LAID-UP IN VERTICAL RUNNING BOND ON FRONT "RADIUS" WALL OF BUILDING

FILLANT AT TOP OF JOINT

4" CONC. SLAB & STEPS W/ 6"x6"-6/6 W.W.F. & PLAIN EDGE ON TREAD NOSING

4" CONC. WALK W/ 6"x6"-6/6 W.W.F.

1" SLOPE

1'-0" CLEAR ACCESS

CONC. HAUNCH TO RECEIVE WALK SLAB.

DATE ISSUED
JUNE, 1972
DECEMBER, 1972

TWIN CINEMA
CONCORD MALL
ELKHART INDIANA

STEENWYK · THRALL
ARCHITECTS
grand rapids, michigan

FILE NO. 7009-4

SHEET NO. 33