


1 ELECTRICAL ROOF PLAN
 SCALE: 1/8" = 1'-0"

- ELECTRICAL GENERAL NOTES:**
- 1 ELECTRICAL CONTRACTOR TO FURNISH NEW DUCT MOUNTED SMOKE DETECTOR. MECHANICAL CONTRACTOR TO INSTALL SMOKE DETECTORS IN RETURN AND/OR SUPPLY AIR DUCTWORK AND PROVIDE WIRING TO FAN INTERLOCK. FOR MORE DETAILED INFORMATION ON SMOKE DETECTORS, AIR SENSORS AND REMOTE SENSORS REFER TO MECHANICAL DRAWINGS "M1.1" AND "M1.2"
 - 2 MOUNT SUPPLY AIR SENSOR IN SUPPLY AIR DROP
 - 3 MOUNT REMOTE SENSORS IN LOCATION SHOWN WITH THERMOSTATS LOCATED IN EQUIPMENT ROOM.
 - 4 PROVIDE NEW ROOF MOUNTED EXHAUST FAN. INTERLOCK EXHAUST FAN WITH NEW EMS FOR CONTROL. EXTEND EXHAUST AIR DUCTWORK UP THRU ROOF IN PRE-FABRICATED INSULATED ROOF CURB TO FAN. ALL ROOF WORK TO BE DONE BY THE LANDLORD'S APPROVED ROOFING CONTRACTOR AT THE GENERAL CONTRACTOR'S EXPENSE.

WINDLE + VOLPE
 ARCHITECTS
 7600 9TH FLOOR
 HOUSTON, TEXAS 77063
 PH 713-955-1390



BEALLS WHITE BOX
CROSSROADS MALL
 GREENVILLE, TEXAS
GREENVILLE PROPERTIES LTD.
 GREENVILLE, TEXAS

DATE	1/11/2015	PROJECT NO.	8-12-05	DRAWN BY	AEP
------	-----------	-------------	---------	----------	-----

ELECTRICAL
 ROOF PLAN
E1.3