



GENERAL NOTES:
 A. PAINT ALL GAS PIPING SAFETY YELLOW.
 B. PIPING WORK IN THE STOCKROOM SHALL NOT BE LOWER THAN 14 FEET ABOVE FINISH FLOOR.

FIRE PROTECTION SYSTEMS:
 A. COMPLY WITH REQUIREMENTS OF NFPA NO. 13 AND THE LOCAL BUILDING CODE FOR INSTALLATION OF FIRE PIPING MATERIALS. INSTALL FIRE SPRINKLER PIPING PRODUCTS WHERE INDICATED, IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS AND IN ACCORDANCE WITH RECOGNIZED INDUSTRY PRACTICES TO ENSURE THAT FIRE SPRINKLER PIPING COMPLIES WITH REQUIREMENTS AND SERVICES INTENDED PURPOSES. THE SYSTEM SHALL BE FACTORY MUTUAL APPROVED THAT MEET THE REQUIREMENTS OF THE STATE BOARD OF INSURANCE.
 B. THE CONTRACTOR SHALL DESIGN, SIZE AND INSTALL ALL PIPING, VALVES AND CONTROLS OR ANY OTHER INCIDENTALS REQUIRED TO INSURE THAT THE PROPOSED CONSTRUCTION COMPLIES WITH NFPA-13.
 C. THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER SHOP DRAWINGS OF PROPOSED INSTALLATION FOR APPROVAL BEFORE CONSTRUCTION BEGINS. THE SYSTEM MUST COMPLY WITH NFPA 13 AND SHALL BE APPROVED BY THE LOCAL FIRE MARSHALL.
 D. ALL PIPING IN THE STOCK ROOM SHALL NOT BE LOWER 14 FEET ABOVE FINISH FLOOR.

1 FLOOR PLAN - PLUMBING
 1/8"=1'-0"



WINDLE + VOLPE
 ARCHITECTS
 7650 NEW BRIDGE, SUITE 900 HOUSTON, TEXAS 77063
 PH 713-255-1390

CAI
 ENGINEERS
 10700 RICHMOND AVE., SUITE 145 GREENVILLE, TEXAS 77030
 TEL: (713) 788-6333 FAX: (713) 788-0009

ROSS BUILD-OUT #1663
CROSSROADS MALL
 GREENVILLE, TEXAS
GREENVILLE PROPERTIES LTD.
 GREENVILLE, TEXAS

DATE	11/22/2013
PROJECT NO.	08-15-01r
DRAWN BY	

FLOOR PLAN
 PLUMBING
P1.0